

<b>BASE BID: Section No. 1 - Abbeville Memorial Cemetery Road, ARC Access Road, Armory Street, N. Trawick Street</b>						
<b>Item No.</b>	<b>Quantity &amp; Units</b>		<b>Description</b>	<b>Unit Price</b>		<b>Total Price</b>
1.	1	L.S.	Mobilization, Including Bonds, Insurance, etc.	\$		\$
2.	1	L.S.	Traffic Control Plan and Implementation, Complete In Place For	\$		\$
3.	11,450	S.Y.	135 Lb. per S.Y. Plant Mix Wearing Surface (424-A), including Tack, Complete In Place For	\$		\$
4.	60	TON	Asphalt Leveling, Complete In Place For	\$		\$
5.	9,450	S.Y.	Bituminous Surface Treatment, ALDOT Type "E", Complete In Place For	\$		\$
6.	35	S.Y.	Leveling Patch, Complete In Place For	\$		\$
7.	200	S.Y.	Wedge Milling Existing Pavement (0"-2"), Complete In Place For	\$		\$
8.	360	S.Y.	Remove Asphalt Paving Due To Root Intrusion To Include Base Replacement, Complete In Place For	\$		\$
9.	290	L.F.	Remove And Replace Standard Curb, Complete In Place For	\$		\$
10.	1	EA.	Water and Gas Valve Boxes Adjusted to Grade, Complete In Place For	\$		\$
11.	1,280	L.F.	Solid Blue Traffic Stripe, Class 1, Type A (4" Wide), Complete In Place For	\$		\$
12.	240	S.F.	Traffic Control Markings, Class 1, Type A, Complete In Place For	\$		\$
<b>TOTAL BASE BID: SECTION NO. 1</b>						<b>\$</b>

<b>BASE BID: Section No. 2 – ARC Parking Lot</b>						
<b>Item No.</b>	<b>Quantity &amp; Units</b>		<b>Description</b>	<b>Unit Price</b>		<b>Total Price</b>
1.	1	L.S.	Mobilization, Including Bonds, Insurance, etc.	\$		\$
2.	4,540	S.Y.	135 Lb. per S.Y. Plant Mix Wearing Surface (424-A), including Tack, Complete In Place For	\$		\$
3.	20	TON	Asphalt Leveling, Complete In Place For	\$		\$
4.	4,540	S.Y.	Bituminous Surface Treatment, ALDOT Type "E", Complete In Place For	\$		\$
5.	20	S.Y.	Wedge Milling Existing Pavement (0"-2"), Complete In Place For			
6.	10	S.Y.	Remove Asphalt Paving Due To Root Intrusion To Include Base Replacement, Complete In Place For	\$		\$
7.	130	L.F.	Remove And Replace Standard Curb, Complete In Place For	\$		\$
8.	3,200	L.F.	Solid White Traffic Stripe, Class 1, Type A (4" Wide), Complete In Place For	\$		\$
9.	75	L.F.	Solid Blue Traffic Stripe, Class 1, Type A (4" Wide), Complete In Place For	\$		\$
10.	120	S.F.	Traffic Control Markings, Class 1, Type A, Complete In Place For	\$		\$
<b>TOTAL BASE BID: SECTION NO. 2</b>						<b>\$</b>

<b>ADDITIVE ALTERNATE NO. 1: Henry County Annex Building Parking Lot</b>							
<b>Item No.</b>	<b>Quantity &amp; Units</b>		<b>Description</b>	<b>Unit Price</b>		<b>Total Price</b>	
1.	1	L.S.	Mobilization, Including Bonds, Insurance, etc.	\$		\$	
2.	380	S.Y.	150 Lb. per S.Y. Plant Mix Wearing Surface (424-A), including Tack, Complete In Place For	\$		\$	
3.	10	TON	Asphalt Leveling, Complete In Place For	\$		\$	
4.	40	S.Y.	Wedge Milling Existing Pavement (0"-2"), Complete In Place For	\$		\$	
5.	340	L.F.	Solid White Traffic Stripe, Class 1, Type A (4" Wide), Complete In Place For	\$		\$	
6.	120	L.F.	Solid Blue Traffic Stripe, Class 1, Type A (4" Wide), Complete In Place For	\$		\$	
7.	3	S.F.	Traffic Control Markings, Class 1, Type A, Complete In Place For	\$		\$	
<b>TOTAL BID ADDITIVE ALTERNATE NO. 1</b>						\$	