

SECTION 01 11 00 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- A. The work of this Project consists of improvements to three wastewater pumping stations which are part of the sewage collection system plus various improvements at the Wastewater Treatment Facility including a new control/lab building, new return sludge pumping station, upgrade to the existing utility pumping station and yard piping improvements.
- B. Also include is the replacement of approximately 760 L.F. of existing 8" gravity sewer on two streets within the Brundidge Sewer System.

1.2 WORK SEQUENCE

- A. The work at the Existing Recirculation Pump Station cannot be commenced until the New RAS Station is complete and operational.
- B. The yard piping modification should also be deferred until the New RAS Station is in service.
- C. There are no restrictions on the scheduling of the New Control/Lab Building or the pump station upgrades and line replacements in the sewer system. The Existing Control Building will remain in service until the New Building is complete and occupied, at which time it is to be demolished.

1.3 CONTRACTOR'S USE OF PREMISES

- A. Contractor shall limit his use of the premises for work and for storage, to allow for Owner occupancy and continuous operation of all facilities in the work area.
- B. Contractor shall coordinate use of premises under direction of Owner.
- C. Contractor shall assume full responsibility for the protection and safekeeping of products under this contract, stored on the site.
- D. Contractor shall move any stored products, under Contractor's control, which interfere with operations of the Owner.

1.4 OWNER OCCUPANCY

- A. Owner will occupy the premises during the entire period of construction for the conduct of his normal operations. Cooperate with Owner's Representative in all construction operations to minimize conflict, and to facilitate Owner usage.

1.5 EMERGENCY RESPONSE PLAN

- A. The Contractor shall develop and implement, prior to the start of work, an emergency response plan for handling spills and overflow of sewage or other materials that will damage the environment. This plan shall include how an immediate response will be achieved. Contractor shall provide the name and telephone number of a local representative that can respond to emergencies on a 24-hour per day basis.

1.6 WORK HOURS

- A. THE Work shall be performed only during the hours of 7 a.m. to 7 p.m., Monday through Saturday. Work may be performed outside this work window under the following conditions:
1. Contractor shall submit written request to Owner requesting different work hours and stating the reason for the request, including why it would be in the best interest of the Owner to approve the request.
 2. Owner gives written approval of the request.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 11 00