

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

<u>ITEM NO.</u>	<u>EST. QTY & UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
1.	1 L.S.	Contractor Mobilization / Demobilization, Including Bonds, Insurance, And All Work Necessary To Mobilize To The Job And Demobilize Upon Completion, Complete For The Lump Sum Price Of	\$ <u>LUMP SUM</u>	\$ _____
2.	1 LS	Replacing All Existing Aeration Equipment To Remain At The Jimmy Carr Wastewater Treatment Facility (JCWWTF), Complete With All Appurtenances, In Place For The Lump Sum Price Of	\$ <u>LUMP SUM</u>	\$ _____
3.	1 LS	Conversion Of The Existing Post-Aeration Basin In Cell 6 Of The JCWWTF To A Chlorine Contact Chamber Using FRP Panels, Complete For The Lump Sum Price Of	\$ <u>LUMP SUM</u>	\$ _____
4.	1 LS	Modification Of The Existing Effluent Weir Box And Cascade Aerator To Include Raising The Elevation Of The Existing Weir Plate, Replacing All Existing Weir Plates On The Cascade Aerator, Repairing The Washed Out Area Around The Effluent Weir Box, Installing New Hand Rail On The Steps To The Cascade Aerator, And Any And All Appurtenances, Complete In Place For The Lump Sum Price Of	\$ <u>LUMP SUM</u>	\$ _____
5.	1 LS	New Chlorination/Dechlorination System Complete, Including The Building, All Equipment, Site Work, Foundation, Piping, Electrical, And All Appurtenances, Complete In Place For The Lump Sum Price Of	\$ <u>LUMP SUM</u>	\$ _____
6.	1 LS	Electrical Construction At The JCWWTF Not Covered In Other Pay Items Including The Replacement Of Panel D With A Junction Box, The Rebuilding Of Panel E, And New Wiring As Called Out In The Drawings, Complete In Place For The Lump Sum Price Of	\$ <u>LUMP SUM</u>	\$ _____

<u>ITEM NO.</u>	<u>EST. QTY & UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
7.	1 LS	New Control Panel And Electrical Service At The North Lagoon, Including New Service Pole, All Related Wiring, Security Light, And Any Other Electrical Work At The North Lagoon Not Covered In Other Pay Items, Complete In Place For The Lump Sum Price Of	\$ LUMP SUM	\$ _____
8.	1 LS	New Ultrasonic Flow Meter At The North Lagoon Including Cleaning And Relining The Parshall Flume Manhole, Wiring, And All Incidentals, Complete In Place For The Lump Sum Price Of	\$ LUMP SUM	\$ _____
9.	1 LS	New Mag Meter On The North Lagoon Effluent Force Main, Including Vault, Hatch, All Wiring, Widening The Lagoon Dike And Incidentals, Complete In Place For The Lump Sum Price Of	\$ LUMP SUM	\$ _____
10.	1 LS	Vegetation Control At The North Lagoon To Include Rooted Vegetation Removal And Limb Trimming At The North Lagoon As Described In Section 31 31 19 Of The Specifications, Complete In Place For The Lump Sum Price Of	\$ LUMP SUM	\$ _____
11.	1 LS	Vegetation Control At The JCWWTF To Include Rooted And Floating Vegetation Removal, Limb Trimming And Hyacinth Removal And Replacement As Described In Section 31 31 19 Of The Specifications, Complete In Place For The Lump Sum Price Of	\$ LUMP SUM	\$ _____
12.	1.25 AC	Forestry Mulching Designated Areas At The North Lagoon, Complete For	\$ /AC	\$ _____
13.	2.25 AC	Forestry Mulching Designated Areas At The JCWWTF, Complete For	\$ /AC	\$ _____

<u>ITEM NO.</u>	<u>EST. QTY & UNIT</u>	<u>DESCRIPTION</u>	<u>UNIT PRICE</u>	<u>TOTAL PRICE</u>
14.	700 DRY TONS	Sludge Solids Removed From Cells Two – Six Of The JCWWTF, Inside The North Lagoon And In Socks On The East Side Of The North Lagoon, Loaded, Hauled, And Land Applied At A Permitted And Approved Site Furnished By The Contractor Or Disposed Of In A Subtitle D Landfill To Include All Labor, Materials, Equipment, Power, Chemicals, Tipping Fees, And All Incidentals, Complete For	\$ _____ /Dry Ton	\$ _____
15.	3,400 LF	Woven Wire Farm Fencing Complete With Fence Fabric, Line Posts, Corner Posts, Braces And Two Strands Of Barbed Wire Per The Drawings, Complete In Place For	\$ _____ /LF	\$ _____
16.	1 EA	Double Swing Vehicular Gate (12') Complete With Gate Posts, Bracing, Hardware, And All Appurtenances, In Place For	\$ _____ /EA	\$ _____
17.	1 EA	Personnel Gate (3'), Complete In Place For	\$ _____ /EA	\$ _____
18.	200 LF	Silt Fence For Temporary Erosion Control, Complete In Place For	\$ _____ /LF	\$ _____
19.	1 AC	Seeding And Mulching Disturbed Areas At The North Lagoon Effluent Pump Station And The Chlorine Building At The JCWWTF, Complete In Place For	\$ _____ /AC	\$ _____
20.	40 CY	Borrow Material Imported From Offsite, Compacted In Place For	\$ _____ /CY	\$ _____
TOTAL BID			\$ _____	

B. Bidder acknowledges that:

1. each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and
2. estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all Unit Price Work will be based on actual quantities, determined as provided in the Contract Documents.