SECTION 01 11 00 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- A. The work of this Contract consists of various improvements at the City of Headland's two Wastewater Treatment Facilities. Much of the work consists of sludge removal and disposal and vegetation control both inside and outside the treatment cells at both facilities. In addition, electrical and controls improvements are called for at the North Lagoon Pretreatment Facility as well as two new flow meters.
- B. The work at the Jimmy Carr Wastewater Treatment Facility (JCWWTF) also includes replacement of all aeration equipment, a new effluent chlorination/dechlorination system, replacement of the boundary fence, new chlorine contact chamber, and some minor electrical work.

1.2 WORK SEQUENCE

- A. The Contractor is to prioritize the installation of the effluent chlorination/dechlorination system to the maximum extent practicable.
- B. No more than one treatment cell shall be removed from service at any one time at the JCWWTF. Otherwise the sequence of work is at the Contractor's discretion.

1.3 CONTRACTOR'S USE OF PREMISES

- A. The Owner requires access to the influent screen area at the JCWWTF and the effluent structure at both facilities on a daily but not continuous basis.
- B. Contractor shall coordinate use of premises under direction of Owner.
- C. Contractor shall assume full responsibility for the protection and safekeeping of products under this contract, stored on the site.
- D. Contractor shall move any stored products, under Contractor's control, which interfere with operations of the Owner.

1.4 OWNER OCCUPANCY

A. Owner will occupy the premises during the entire period of construction for the conduct of his normal operations. Cooperate with Owner's Representative in all construction operations to minimize conflict, and to facilitate Owner usage.

SUMMARY OF WORK 01 11 00 - 1

1.5 EMERGENCY RESPONSE PLAN

A. The Contractor shall develop and implement, prior to the start of work, an emergency response plan for handling spills and overflow of sewage or other materials that will damage the environment. This plan shall include how an immediate response will be achieved. Contractor shall provide the name and telephone number of a local representative that can respond to emergencies on a 24-hour per day basis.

1.6 WORK HOURS

A. There will be no restrictions on the Contractor's work hours on this project.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 11 00

SUMMARY OF WORK 01 11 00 - 2