

## SECTION 01 11 00 - SUMMARY OF WORK

### PART 1 - GENERAL

#### 1.1 WORK COVERED BY CONTRACT DOCUMENTS

- A. The work of this contract consists of furnishing and installing concrete slope paving inside the west dike of the emergency storage pond at the Donalsonville Water Pollution Control Plant. Also included is the repair of the existing concrete slope paving on the dike to remain.

#### 1.2 WORK SEQUENCE

- A. The first work of this contract will be the thorough cleaning of the existing concrete slope paving to be repaired and reconditioned. Document the condition of the existing concrete by video prior to beginning the excavation for slope paving or compacted clay. Defer concrete repair until the new concrete or clay liner is in place and compacted in the case of clay should the concrete to remain be damaged during grading.

#### 1.3 CONTRACTOR'S USE OF PREMISES

- A. Contractor shall have unfettered access to the site to conduct his operations subject to non-interference with the Owner's normal activities operating the plant.
- B. Contractor shall assume full responsibility for the protection and safekeeping of products under this contract stored on site.

#### 1.4 WORK HOURS

- A. THE Work shall be performed only during the hours of 7 a.m. to 7 p.m., Monday through Saturday. Work may be performed outside this work window under the following conditions:
  - 1. Contractor shall submit written request to Owner requesting different work hours and stating the reason for the request, including why it would be in the best interest of the Owner to approve the request.
  - 2. Owner gives written approval of the request.

### PART 2 - PRODUCTS (NOT USED)

### PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 11 00

**[This page intentionally left blank for duplex printing]**