

SECTION 01 11 00 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- A. The work of this Project consists of improvements to three wastewater pumping stations which are part of the sewage collection system plus various improvements at the Wastewater Treatment Facility including a new return sludge pumping station, upgrade to the existing utility pumping station and yard piping improvements.
- B. Also included is the replacement of approximately 760 L.F. of existing 8" gravity sewer on two streets within the Brundidge Sewer System.

1.2 WORK SEQUENCE

- A. The Owner will award separate contracts for other work at the Wastewater Treatment Facility to be performed concurrently with the work of this Contract. This work includes the construction of a new control building and the site work associated with that, the demolition of the existing control building, the removal and replacement of most of the onsite pavement and the removal and disposal of all accumulated sludge in existing Cells One and Seven. Some of this work directly impacts the work of this Contract.

The new return sludge pumping station in this Contract is located immediately adjacent to new heavy duty paving and the 8" force main from that station crosses underneath the new paving. Consequently, the installation of the new wet well, the 10' x 20' concrete slab and the new 8" return sludge force main should be the first work of this Contract.

In addition, the existing recirculation pump station cannot be removed from service, nor can it be used to drain Cells One and/or Seven until the new RAS station is in service. All the more reason why the construction of this station must be the first work of this Contract.

- B. The yard piping modification should also be deferred until the New RAS Station is in service.
- C. There are no restrictions on the scheduling of the pump station upgrades and line replacements in the sewer system.

1.3 CONTRACTOR'S USE OF PREMISES

- A. Contractor shall limit his use of the premises for work and for storage, to allow for Owner occupancy and continuous operation of all facilities in the work area.
- B. Contractor shall coordinate use of premises under direction of Owner.
- C. Contractor shall assume full responsibility for the protection and safekeeping of products under this contract, stored on the site.

- D. Contractor shall move any stored products, under Contractor's control, which interfere with operations of the Owner.

1.4 OWNER OCCUPANCY

- A. Owner will occupy the premises during the entire period of construction for the conduct of his normal operations. Cooperate with Owner's Representative in all construction operations to minimize conflict, and to facilitate Owner usage.

1.5 EMERGENCY RESPONSE PLAN

- A. The Contractor shall develop and implement, prior to the start of work, an emergency response plan for handling spills and overflow of sewage or other materials that will damage the environment. This plan shall include how an immediate response will be achieved. Contractor shall provide the name and telephone number of a local representative that can respond to emergencies on a 24-hour per day basis.

1.6 WORK HOURS

- A. THE Work shall be performed only during the hours of 7 a.m. to 7 p.m., Monday through Saturday. Work may be performed outside this work window under the following conditions:
 - 1. Contractor shall submit written request to Owner requesting different work hours and stating the reason for the request, including why it would be in the best interest of the Owner to approve the request.
 - 2. Owner gives written approval of the request.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 11 00