

Bidder agrees to perform all the work described in the specification and shown on the plans, for the following unit prices:

**BID PROPOSAL**

| <b>SECTION A. CDBG ELIGIBLE</b> |                  |    |   |             |
|---------------------------------|------------------|----|---|-------------|
| Item No.                        | Est. Qty. & Unit |    | Description   | Total Price |
| 1.                              | Lump Sum         |    | Contractor Mobilization/Demobilization Including Bonds, Insurance, and All Work Associated With Mobilizing To The Job Site And Demobilizing Upon Completion, Complete For The Lump Sum Price Of |             |
|                                 |                  |    |   | Lump Sum \$ |
| 2.                              | 4,600            | SY | Milling Existing Asphalt Pavement, Complete For   | \$ /SY \$   |
| 3.                              | 3,750            | SY | Excavation For New Heavy Duty Pavement Including Preparing Subgrade For Crushed Aggregate Base And Placing Excavated Material At Designated Locations On-Site, Complete In Place For            | \$ /SY \$   |
| 4.                              | 3,750            | SY | 275 LB/SY 424B589 Asphalt Lower Binder, 1" Max Aggregate Size, Mix ESAL Range E, Complete In Place For  | \$ /SY \$   |
| 5.                              | 3,750            | SY | 220 LB/SY 424B281 Superpave Bituminous Concrete Upper Binder, 1" Max Aggregate Size, ESAL Range E, Complete In Place For  | \$ /SY \$   |
| 6.                              | 7,700            | SY | 165 LB/SY 424A281 Superpave Bituminous Concrete Wearing Surface, 3/4" Max Aggregate Size, ESAL Range E, Complete In Place For   | \$ /SY \$   |
| 7.                              | 1,200            | SY | 6" Crushed Aggregate Base Course For Standard Base And Paving, Compacted In Place For   | \$ /SY \$   |
| 8.                              | 3,900            | SY | 12" Crushed Aggregate Base Course Placed And Compacted In Two 6" Lifts For Heavy Duty Base And Paving, Complete In Place For  | \$ /SY \$   |
| 9.                              | 9,300            | SY | Bituminous Tack Coat, Complete In Place For   | \$ /SY \$   |
| 10.                             | 1,100            | SY | Bituminous Surface Treatment Following Milling, Complete In Place For   | \$ /SY \$   |
| 11.                             | Lump Sum         |    | Striping of New Paving Around The Control Building, Complete For The Lump Sum Price Of  |             |
|                                 |                  |    |   | Lump Sum \$ |
| 12.                             | Lump Sum         |    | Vegetation Removal In Cell Seven, Complete For The Lump Sum Price Of  |             |
|                                 |                  |    |   | Lump Sum \$ |

| Item No.                          | Est. Qty. & Unit |          | Description  | Unit Price  | Total Price |
|-----------------------------------|------------------|----------|--|-------------|-------------|
| 13.                               | 460              | Dry Tons | Sludge Solids Removed From Cells One and Seven, Loaded, Hauled, And Either Land Applied At A Permitted And Approved Site Furnished By The Contractor Or Disposed Of In A Subtitle D Landfill To Include All Labor, Materials, Equipment, Power, Chemicals, Tipping Fees, And All Incidentals, Complete In Place For  | \$ /Dry Ton | \$          |
| 14.                               | 5,000            | SY       | Grassing Consisting Of Seeding Disturbed Areas Around Cells One Through Seven And Other Locations As Directed by The Engineer, Complete In Place For   | \$ /AC      | \$          |
| 15.                               | 1,000            | SY       | Erosion Control Blanket Installed Over Seeded Lagoon Front Slopes As Directed By The Engineer, Complete In Place For   | \$ /SY      | \$          |
| 16.                               | 4,000            | SY       | Mulch Placed Over Seeded Disturbed Areas Other Than Lagoon Front Slopes, Complete In Place For   | \$ /SY      | \$          |
| 17.                               | 200              | CY       | Topsoil Borrow Imported From Off-Site Used For Lagoon Dike Replenishment Or At Other Locations As Directed By The Engineer (Loose Truck Measure), Spread and Compacted In Place For  | \$ /CY      | \$          |
| 18.                               | 100              | CY       | General Borrow Imported From Off-Site (Loose Truck Measure), Complete In Place For   | \$ /CY      | \$          |
| 19.                               | 400              | LF       | Silt Fence For Erosion Control, Complete In Place For  | \$ /LF      | \$          |
| 20.                               | Lump Sum         |          | Removal And Disposal Of Existing Water Meter Vault, Removal And Relocation Of Existing Meter/Backflow Preventer And Replacement With 3” CL 200 PVC, Furnish And Install New 4’ x 6’ Precast Concrete Vault At Location Shown On The Drawings Over Relocated Meter/Backflow Preventer, Complete And In Place With All Incidentals For the Lump Sum Price Of | Lump Sum    | \$          |
| SUBTOTAL SECTION A. CDBG ELIGIBLE |                  |          |  |             | \$          |

| SECTION B. NON-CDBG ELIGIBLE (OAK STREET)          |                  |    |  |            |             |
|--|------------------|----|--|------------|-------------|
| Item No.   | Est. Qty. & Unit |    | Description  | Unit Price | Total Price |
| 1.   | 4,250            | SY | Milling Existing Asphalt Pavement, Complete For  | \$ /SY     | \$          |
| 2.   | 4,250            | SY | Bituminous Surface Treatment Following Milling, Complete In Place For  | \$ /SY     | \$          |
| 3.   | 4,250            | SY | Bituminous Tack Coat, Complete In Place For  | \$ /SY     | \$          |
| 4.   | 4,250            | SY | 165 LB/SY 424A281 Superpave Bituminous Concrete Wearing Surface, 3/4" Max Aggregate Size ESAL Range E, Complete In Place For | \$ /SY     | \$          |
| 5.   | 300              | LF | Remove And Replace Concrete Curb At Locations Directed By The Engineer, Complete In Place For                                | \$ /LF     | \$          |
| 6.   | Lump Sum         |    | Traffic Control On Oak Street Including Signs, Flagging, Etc., Complete For The Lump Sum Price Of                            | Lump Sum   |             |
| SUBTOTAL SECTION B. NON-CDBG ELIGIBLE (OAK STREET) |                  |    |  |            | \$          |
| TOTAL BID SECTIONS "A" PLUS "B"                    |                  |    |  |            | \$          |

TOTAL BID AMOUNT SECTIONS "A" PLUS "B" IS: \_\_\_\_\_

\_\_\_\_\_ DOLLARS & \_\_\_\_\_ CENTS.

(Amounts are to be shown in both words and figures. In case of discrepancy, the amount shown in words will govern.)

The above unit prices shall include all labor, materials, bailing, shoring, removal, overhead, profit, insurance, etc., to cover the finished work of the several kinds called for.

Bidder understands that the Owner reserves the right to reject any or all bids and to waive any informalities in the bidding.

The bidder agrees that this bid shall be good and may not be withdrawn for a period of 45 calendar days after the scheduled closing time for receiving bids.