

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "A" – CLEARING AND GRUBBING, DEMOLITION, SITE GRADING AND EROSION CONTROL						
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price		Bid Amount
1.	Lump Sum	Mobilization to Include Bonds, Insurance, Permits, Licenses, Etc., Complete In Place For	\$	LUMP SUM	\$	
2.	Lump Sum	Compliance With ADEM Site Disturbance Permitting And Inspections, Complete In Place For	\$	LUMP SUM	\$	
3.	Lump Sum	Clearing And Grubbing to Include Demolition and Removals, Complete In Place For	\$	LUMP SUM	\$	
4.	Lump Sum	Strip Top 6" of Topsoil, Stockpile, Spread For Grassing, Unclassified Excavation (Cut & Fill), Material Processing, As Required To Grade Site, Complete In Place For	\$	LUMP SUM	\$	
5.	2,500 C.Y.	Excavating Unsuitable Material as Approved by the Engineer, Hauling Off Site, Fill with Suitable Material to Include Compaction, Complete In Place For	\$		\$	
6.	5,000 Gals.	Water as Required During Grading Operations to Control Dust, When Requested by the Engineer, Complete In Place For	\$		\$	
7.	Lump Sum	Gravel Construction Entrance/Exit Pad, Complete In Place For	\$	LUMP SUM	\$	
8.	2,530 L.F.	Silt Fencing, Complete In Place For	\$		\$	
9.	50 Ea.	Synthetic Hay Bales, Complete In Place For	\$		\$	
10.	240 L.F.	Wattle Inlet Protection, Complete In Place For	\$		\$	
11.	15 Acs	Seeding & Mulching, Complete In Place For	\$		\$	
12.	2,700 S.Y.	Solid Sodding to Prevent Erosion, Complete In Place For	\$		\$	
13.	20,100 S.Y.	Solid Sodding (Athletic Fields), Complete In Place For	\$		\$	
14.	Lump Sum	Owner's Contingency Allowance as Described in Section 00 72 00, Article 13.02.C, Complete In Place For	\$	LUMP SUM	\$	25,000.00
TOTAL BID SECTION "A" IS \$ _____						

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "B" – BASE, PAVING, STRIPING, TRAFFIC MARKINGS, TRAFFIC LEGENDS & SIGNAGE						
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price		Bid Amount
1.	14,325 S.Y.	6" Subgrade Processing to Prepare Subgrade for Base, Complete In Place For	\$		\$	
2.	14,325 S.Y.	6" Crushed Aggregate Base Course, Complete In Place For	\$		\$	
3.	4,560 L.F.	6" X 18" Concrete Curb, Complete In Place For	\$		\$	
4.	420 L.F.	6" X 12" Concrete Header Curb, Complete In Place For	\$		\$	
5.	14,325 S.Y.	Prime Coat, Complete In Place For	\$		\$	
6.	13,500 S.Y.	Bituminous Upper Binder, Complete In Place For	\$		\$	
7.	13,500 S.Y.	Tack Coat, Complete In Place For	\$		\$	
8.	13,500 S.Y.	Bituminous Wearing Surface, Complete In Place For	\$		\$	
9.	32 S.Y.	Concrete Flumes, Complete In Place For	\$		\$	
10.	3 Ea.	Curb Inlets (Type S-1, 1-Wing), Complete In Place For	\$		\$	
11.	1 Ea.	Junction Box (JB-3), Complete In Place For	\$		\$	
12.	54 Ea.	Compaction Tests for Subgrade and Aggregate Base, Complete In Place For	\$		\$	
13.	10 EA.	Concrete Wheel Stops, Complete In Place For	\$		\$	
14.	150 L.F.	Double Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide), Complete In Place For	\$		\$	
15.	70 L.F.	Solid White, Class 2, Type A Traffic Stripe (5" Wide), Complete In Place For	\$		\$	
16.	105 L.F.	Dotted White, Class 2, Type A Traffic Stripe (5" wide), Complete In Place For	\$		\$	
17.	135 S.F.	Traffic Control Markings, Class 2, Type A, Complete In Place For	\$		\$	
18.	25 S.F.	Traffic Control Legends, Class 2, Type A, Complete In Place For	\$		\$	
19.	4,250 L.F.	Solid White Parking Striping, Class 1, Type B (4" Wide), Complete In Place For	\$		\$	

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "B" – BASE, PAVING, STRIPING, TRAFFIC MARKINGS, TRAFFIC LEGENDS & SIGNAGE						
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price		Bid Amount
20.	370 L.F.	Solid Blue H/C Stripe, Class 1, Type B (4" Wide), Complete In Place For	\$		\$	
21.	1,100 S.F.	Solid White Hatched Striping, Class 1, Type B (4" Wide), Complete In Place For	\$		\$	
22.	670 S.F.	Solid Blue Hatched Striping, Class 1, Type B (4" Wide), Complete In Place For	\$		\$	
23.	10 EA.	Handicap Painted Symbol, Class 1, Type B, Complete In Place For	\$		\$	
24.	10 EA.	Handicap Signs, Complete In Place For	\$		\$	
25.	124 S.F.	Truncated Domes, Complete In Place For	\$		\$	
26.	3 EA.	ALDOT 710A-160 Stop Sign with 710B-021 Post, Complete In Place For	\$		\$	
27.	1 EA.	ALDOT R1-2 Yield Sign with 710B-021 Post, Complete In Place For	\$		\$	
28.	4 EA.	ALDOT R2-1 Speed Limit Sign with 710B-021 Post, Complete In Place For	\$		\$	
29.	Lump Sum	Owners Contingency Allowance, As Described in Section 00 72 00, Article 13.02.C, Complete In Place For	\$	LUMP SUM	\$	25,000.00
<p style="text-align: right;">TOTAL BID SECTION "B" IS \$ _____</p>						

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "C" – STORM DRAINAGE, WATER AND SEWER UTILITIES						
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price		Bid Amount
1.	216 L.F.	19 x 30" R.C. Pipe, Class III Arched Pipe, with Gasketed Joints, Complete In Place For	\$		\$	
2.	1,032 L.F.	24" Diameter R.C. Pipe, Class III, with Gasketed Joints, Complete In Place For	\$		\$	
3.	816 L.F.	18" Diameter R.C. Pipe, Class III, with Gasketed Joints, Complete In Place For	\$		\$	
4.	770 L.F.	24" Diameter CPP (HP Dual Wall), Complete In Place For	\$		\$	
5.	264 L.F.	18" Diameter CPP (HP Dual Wall), Complete In Place For	\$		\$	
6.	336 L.F.	15" Diameter CPP (HP Dual Wall), Complete In Place For	\$		\$	
7.	1 EA.	Open Throat Inlet Box, Complete In Place For	\$		\$	
8.	19 EA.	Grate Inlets, Complete In Place For	\$		\$	
9.	2 EA.	Storm Junction Boxes, Complete In Place For	\$		\$	
10.	1 EA.	Outlet Structure with Piping, Complete In Place For	\$		\$	
11.	1 EA.	42" CPP Sloped Paved Headwall, Complete In Place For	\$		\$	
12.	2 EA.	19" x 30" RCP Sloped Paved Headwall, Complete In Place For	\$		\$	
13.	4 EA.	24" Diameter Pipe Sloped Paved Headwall, Complete In Place For	\$		\$	
14.	5 EA.	18" and 15" Diameter Pipe Sloped Paved Headwall, Complete In Place For	\$		\$	
15.	15 S.Y.	Rip-Rap with Filter Fabric, Complete In Place For	\$		\$	
16.	40 L.F.	10" Steel Casing (0.250" Wall Thick), Jacked and Bored, Complete In Place For	\$		\$	
17.	1 EA.	6" X 6" Tapping Sleeve w/6" Gate Valve & Box, Complete In Place For	\$		\$	
18.	1 EA.	4" Compound Water Meter, Concrete Vault with H20 Rated Hatch, Complete In Place For	\$		\$	

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "C" – STORM DRAINAGE, WATER AND SEWER UTILITIES						
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price		Bid Amount
19.	7 EA.	Hose Bibb (Freeze Proof Hydrant) With Post, Slab, Fittings, Straps, Etc., Complete In Place For	\$		\$	
20.	970 L.F.	6" PVC Water Main (Class 200) with Tracer Wire, Complete In Place For	\$		\$	
21.	6 L.F.	6" D.I. Water Main Pipe, with Restrained Joints, Complete In Place For	\$		\$	
22.	4 EA.	6" Gate Valves with Box, Complete In Place For	\$		\$	
23.	1 EA.	Fire Hydrant (3-Way), Complete In Place For	\$		\$	
24.	1,300 L.F.	3" PVC Water Main (Class 200) with Tracer Wire, Complete In Place For	\$		\$	
25.	7 EA.	3" Gate Valves with Box, Complete In Place For	\$		\$	
26.	80 L.F.	2" PVC Water Main (Class 200) with Tracer Wire, Complete In Place For	\$		\$	
27.	7 EA.	2" Ball Valve (Water) In Box, Complete In Place For	\$		\$	
28.	1,100 Lbs.	D.I. Pipe Fittings (Water), Complete In Place For	\$		\$	
29.	1,380 L.F.	2-1/2" PVC Force Main (Class 200) with Tracer Wire, Including Fittings, Complete In Place For	\$		\$	
30.	1 EA.	2-1/2" Ball Valve (Sewer) In Box, Complete In Place For	\$		\$	
31.	Lump Sum	Grinder Pump Station with Backboard (2 HP-Dual Pump) with Controls, Disconnect, Complete In Place For	\$	LUMP SUM	\$	
32.	Lump Sum	Flushing, Pressure Testing and Bacteriological Testing of Water Mains, Complete In Place For	\$	LUMP SUM	\$	
33.	Lump Sum	Flushing and Pressure Testing of Force Mains, Complete In Place For	\$	LUMP SUM	\$	
34.	Lump Sum	As-Built of Project to Include Coordinates of Water Mains, Force Mains, Fittings, and Valves, Complete In Place For	\$	LUMP SUM	\$	

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "C" – STORM DRAINAGE, WATER AND SEWER UTILITIES					
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price	Bid Amount
35.	Lump Sum	Owner's Contingency Allowance as Described in Section 00 72 00, Article 13.02.C, Complete In Place For	\$	LUMP SUM	\$ 15,000.00
TOTAL BID SECTION "C" IS \$ _____					

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "D" – WALKWAYS, STEPS, RAMP AND RETAINING WALLS						
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price		Bid Amount
1.	195 S.Y.	Concrete Ramps (Sheet CSI.4) to Include Reinforcing, Concrete Walls and Footers, Complete In Place For	\$		\$	
2.	43 C.Y.	Concrete Steps (Sheet CSI.7) to Include Reinforcing, Concrete Walls and Footers, Complete In Place For	\$		\$	
3.	105 L.F.	Aluminum Handrails, Complete In Place For	\$		\$	
4.	310 L.F.	Aluminum Guardrails, Complete In Place For	\$		\$	
5.	355 S.Y.	Concrete Walkways, 20' Wide (8" Thick) with Reinforcement, Joints, Etc. Complete In Place For	\$		\$	
6.	340 S.Y.	Concrete Walkways, 14.5' Wide (8" Thick) with Reinforcement, Joints, Etc. Complete In Place For	\$		\$	
7.	1,495 S.Y.	Concrete Walkways, 10' Wide (8" Thick) with Reinforcement, Joints, Etc., Complete In Place For	\$		\$	
8.	932 S.Y.	Concrete Walkways, 8' Wide (4" Thick) with Reinforcement, Joints, Etc., Complete In Place For	\$		\$	
9.	37 S.Y.	Concrete Walkways, 6' Wide (4" Thick) with Reinforcement, Joints, Etc., Complete In Place For	\$		\$	
10.	10 S.Y.	Concrete Transformer Pad (APC) with Reinforcement, Complete In Place For	\$		\$	
11.	27 S.Y.	Concrete Dumpster Pad with Reinforcement, Joints, Etc., Complete In Place For	\$		\$	
12.	2,370 S.Y.	Concrete Bleacher Pads (4" Thick) with Reinforcement, Joints, Etc., Complete In Place	\$		\$	
13.	310 C.Y.	Concrete Retaining Walls & Footers, with Reinforcement, Joints, Finishing, Etc., Complete In Place For	\$		\$	
14.	140 C.Y.	#57 Stone Drainage Filter For Retaining Walls and Ramp Walls, Complete In Place For	\$		\$	

The Bidder shall not include in the prices bid the sales and use tax on products which are exempt from sales and use tax.

BID SECTION "D" – WALKWAYS, STEPS, RAMP AND RETAINING WALLS						
Item No.	Estimated Quantity & Unit	Description		Bid Unit Price		Bid Amount
15.	60 EA.	Compaction Tests For Concrete Footers, Walkways, Ramps, Steps, Bleacher Pads, Etc., Complete In Place For	\$		\$	
16.	15 EA.	Backfill Compaction Tests on Retaining Walls, Ramp Walls, Step Walls, Etc., Complete In Place For	\$		\$	
17.	Lump Sum	Owner's Contingency Allowance as Described in Section 00 72 00, Article 13.02.C, Complete In Place For	\$	LUMP SUM	\$	25,000.00
<p style="text-align: right;">TOTAL BID SECTION "D" IS \$ _____</p>						

BID SECTION "E" – SUMMARY OF BIDS	
TOTAL BID SECTION "A" IS	\$ _____
TOTAL BID SECTION "B" IS	\$ _____
TOTAL BID SECTION "C" IS	\$ _____
TOTAL BID SECTION "D" IS	\$ _____
	=====
TOTAL COMBINED BID IS	\$ _____

TOTAL BID AMOUNT IS _____

_____ DOLLARS

AND _____ CENTS.