

CONTRACT SCHEDULE

WITH SPECIAL REGARD TO SPECIFICATION SECTION 102.06, "PREPARATION OF PROPOSAL", **AS REVISED BY THE SPECIAL PROVISIONS**, THE FOLLOWING REPRESENTS THE BIDDER'S SCHEDULE OF CONTRACT UNIT PRICES FOR THIS PROPOSAL (bidder to complete below):

LINE NO.	ITEM NO.	DESCRIPTION	QUANTITY & UNIT		UNIT PRICE	AMOUNT BID
1	201A-002	CLEARING AND GRUBBING (MAXIMUM ALLOWABLE BID \$8,000.00 PER ACRE) (APPROXIMATELY 1 ACRE)	1	LS	\$	\$
2	206C-000	REMOVING CONCRETE SIDEWALK	23	SQ YD	\$	\$
3	206C-010	REMOVING CONCRETE DRIVEWAY	164	SQ YD	\$	\$
4	206D-002	REMOVING CURB	80	LIN FT	\$	\$
5	206D-003	REMOVING CURB AND GUTTER	231	LIN FT	\$	\$
6	206E-042	REMOVING INLETS (PARTIAL)	2	EA	\$	\$
7	209A-000	MAILBOX RESET, SINGLE	3	EA	\$	\$
8	210A-000	UNCLASSIFIED EXCAVATION	180	CU YD	\$	\$
9	210D-021	BORROW EXCAVATION (LOOSE TRUCKBED MEASUREMENT) (A4 OR BETTER)	50	CU YD	\$	\$
10	424B-639	SUPERPAVE BITUMINOUS CONCRETE UPPER BINDER LAYER, PATCHING, 3/4" MAXIMUM AGGREGATE SIZE MIX, ESAL RANGE A/B	25	TON	\$	\$
11	517D-002	GALVANIZED STEEL SIDEWALK HANDRAIL	40	LIN FT	\$	\$
12	600A-000	MOBILIZATION	1	LS	\$	\$
13	614B-000	REINFORCED SLOPE PAVING	10	CU YD	\$	\$
14	618A-000	CONCRETE SIDEWALK, 4" THICK	800	SQ YD	\$	\$
15	618A-001	CONCRETE SIDEWALK, 6" THICK	52	SQ YD	\$	\$
16	618B-003	CONCRETE DRIVEWAY, 6" THICK (INCLUDES WIRE MESH)	710	SQ YD	\$	\$
17	618C-001	DETECTABLE WARNING SURFACE	130	SQ FT	\$	\$
18	618D-000	CURB RAMP	125	SQ YD	\$	\$
19	620A-000	MINOR STRUCTURE CONCRETE	5	CU YD	\$	\$
20	621C-053	INLETS, TYPE SPECIAL (PARTIAL)	2	EA	\$	\$
21	623B-002	CONCRETE CURB, TYPE A	74	LIN FT	\$	\$
22	641R-510	3/4 INCH WATER METER AND BOX RESET	8	EA	\$	\$
23	641S-500	VALVE BOX RESET	4	EA	\$	\$
24	650A-000	TOPSOIL	120	CU YD	\$	\$
25	652A-100	SEEDING	1	AC	\$	\$
26	654A-000	SOLID SODDING	1200	SQ YD	\$	\$
27	656A-010	MULCHING	1	AC	\$	\$

CONTRACT SCHEDULE

WITH SPECIAL REGARD TO SPECIFICATION SECTION 102.06, "PREPARATION OF PROPOSAL", **AS REVISED BY THE SPECIAL PROVISIONS**, THE FOLLOWING REPRESENTS THE BIDDER'S SCHEDULE OF CONTRACT UNIT PRICES FOR THIS PROPOSAL (bidder to complete below):

LINE NO.	ITEM NO.	DESCRIPTION	QUANTITY & UNIT		UNIT PRICE	AMOUNT BID
28	659C-002	EROSION CONTROL PRODUCT, TYPE S2	100	SQ YD	\$	\$
29	665J-002	SILT FENCE	340	LIN FT	\$	\$
30	665O-001	SILT FENCE REMOVAL	340	LIN FT	\$	\$
31	665P-005	INLET PROTECTION, STAGE 3 OR 4	3	EA	\$	\$
32	665Q-002	WATTLE	200	LIN FT	\$	\$
33	680A-001	GEOMETRIC CONTROLS	1	LS	\$	\$
34	703A-002	TRAFFIC CONTROL MARKINGS, CLASS 2, TYPE A	610	SQ FT	\$	\$
35	701H-001	SOLID TRAFFIC STRIPE REMOVED (PLASTIC)	40	LIN FT	\$	\$
36	710A-163	CLASS 10 ALUMINUM FLAT SIGN PANELS (TYPE XI BACKGROUND)	54	SQ FT	\$	\$
37	710B-021	ROADWAY SIGN POST (#3 U CHANNEL, GALVANIZED STEEL OR 2", 14 GA SQUARE TUBULAR STEEL)	84	LIN FT	\$	\$
38	711A-000	ROADWAY SIGN RELOCATION	1	LS	\$	\$
39	740B-000	CONSTRUCTION SIGNS	352	SQ FT	\$	\$
40	740D-000	CHANNELIZING DRUMS	50	EA	\$	\$
41	740E-000	CONES (36 INCHES HIGH)	100	EA	\$	\$
TOTAL BID AMOUNT: \$						