

SECTION 01 11 00 - SUMMARY OF WORK

PART 1 - GENERAL

1.1 WORK COVERED BY CONTRACT DOCUMENTS

- A. The work covered by these Contract Documents include all labor, materials, equipment, and miscellaneous work items required for the construction of a 250 GPM Irrigation Well on-line and tested complete with pump, electrical controls, piping, screens, gravel pack, site work and other associated appurtenances as indicated within the project plans and project manual.

1.2 MATERIAL SUPPLIED BY OWNER

- A. The following building material shall be supplied by the Owner and included with Alternate No. 1 if awarded. The material will be delivered to a single location within the project limits. All additional material required to construct the well building shall be supplied by the Contractor.

QUANTITY	MATERIAL
Material Description	
90	U Block
78	Half Block
166	6" Full Block
36	8" Full Block
3,510	Red Colonial Brick
37	Color Masonry (70 pound bag)
1	PTAC Unit
1	Door Frame
1	Hollow Metal Door
1	Type B4EM Fixture - 96-4-L40/840-DCL-EM-1 OW-DIM-UNV
1	Panel RPB Siemans Panel CAN - B32 - Type MEMA 1 - 32" H x 20" x 5-3/4" D
1	Panel RPB Siemans Panel Interior
1	Panel RPB Siemans Panel Cover - SB3H

1.3 PROJECT SALES TAX EXEMPTION

- A. The project qualifies for sales tax exemption through State of Alabama Rule No. 810-6-3-.77. All pricing included on the Bid Form shall **exclude** sales tax in accordance with Project Manual Section 00 73 00 – SUPPLEMENTARY CONDITIONS, Article 7, Paragraph 7.09.

1.4 COORDINATION AND WORK SEQUENCE

- A. The project shall be constructed in a sequence that will provide the least inconvenience to the Enterprise Multipurpose Recreational Complex and the Enterprise State Community College's adjacent baseball/softball complex.

1.5 CONTRACTOR'S USE OF PREMISES

- A. Contractor shall limit his use of the premises for work and for storage, to allow for Owner occupancy and continuous operation of all facilities in the work areas.
- B. Contractor shall coordinate use of premises under direction of Owner.
- C. Contractor shall assume full responsibility for the protection and safekeeping of all stored products under this contract.
- D. Contractor shall move any stored products, under Contractor's control, which interfere with operations of the Owner.

1.6 EMERGENCY RESPONSE PLAN

- A. The Contractor shall develop and implement, prior to the start of work, an emergency response plan for handling problems. This plan shall include how an immediate response will be achieved. Contractor shall provide the name and telephone number of a local representative that can respond to emergencies on a 24-hour per day basis.

1.7 WORK HOURS

- A. THE Work shall be performed only during the hours of 7 a.m. to 5 p.m. Work may be performed outside this work window under the following conditions:
 - 1. Contractor shall submit written request to Owner requesting different work hours and stating the reason for the request, including why it would be in the best interest of the Owner to approve the request.
 - 2. Owner gives written approval of the request.

PART 2 - PRODUCTS (NOT USED)

PART 3 - EXECUTION (NOT USED)

END OF SECTION 01 11 00