

CONTRACT SCHEDULE

WITH SPECIAL REGARD TO SPECIFICATION SECTION 102.06, "PREPARATION OF PROPOSAL", **AS REVISED BY THE SPECIAL PROVISIONS**, THE FOLLOWING REPRESENTS THE BIDDER'S SCHEDULE OF CONTRACT UNIT PRICES FOR THIS PROPOSAL (bidder to complete below):

| LINE NO. | ITEM NO. | DESCRIPTION | QUANTITY & UNIT | | UNIT PRICE | AMOUNT BID |
|----------|----------|--|-----------------|-------------|------------|------------|
| 1 | 201A-002 | Clearing and Grubbing (Maximum Allowable Bid \$ 8,000.00 per Acre) (Approximately 1 Acre) | 1 | LUMP SUM | \$ | \$ |
| 2 | 206C-010 | Removing Concrete Driveway | 190 | SQUARE YARD | \$ | \$ |
| 3 | 206D-002 | Removing Curb | 70 | LINEAR FOOT | \$ | \$ |
| 4 | 206D-003 | Removing Curb and Gutter | 40 | LINEAR FOOT | \$ | \$ |
| 5 | 206E-000 | Removing Headwalls | 4 | EACH | \$ | \$ |
| 6 | 206E-001 | Removing Inlets | 1 | EACH | \$ | \$ |
| 7 | 209A-000 | Mailbox Reset, Single | 4 | EACH | \$ | \$ |
| 8 | 210A-000 | Unclassified Excavation | 250 | CUBIC YARD | \$ | \$ |
| 9 | 210D-021 | Borrow Excavation (Loose Truckbed Measurement) (A4 or Better) | 815 | CUBIC YARD | \$ | \$ |
| 10 | 214A-000 | Structure Excavation | 228 | CUBIC YARD | \$ | \$ |
| 11 | 214B-001 | Foundation Backfill, Commerical | 53 | CUBIC YARD | \$ | \$ |
| 12 | 305A-051 | Coarse Aggregate, Section 801, For Miscellaneous Use | 211 | CUBIC YARD | \$ | \$ |
| 13 | 424B-639 | Superpave Bituminous Concrete Upper Binder Layer, Patching 3/4" Maximum Aggregate Size Mix, ESAL A/B | 10 | TON | \$ | \$ |
| 14 | 502A-000 | Steel Reinforcement | 1,980 | POUNDS | \$ | \$ |
| 15 | 517D-002 | Galvanized Steel Sidewalk Handrail | 120 | LINEAR FOOT | \$ | \$ |
| 16 | 524B-010 | Culvert Concrete Extension | 20 | CUBIC YARD | \$ | \$ |
| 17 | 530A-101 | 18" Roadway Pipe (Class 3 R.C.) (Extension) | 5 | LINEAR FOOT | \$ | \$ |
| 18 | 530A-103 | 30" Roadway Pipe (Class 3 R.C.) (Extension) | 14 | LINEAR FOOT | \$ | \$ |
| 19 | 535A-078 | 15" Side Drain Pipe (Class 3 R.C.) | 41 | LINEAR FOOT | \$ | \$ |
| 20 | 600A-000 | Mobilization | 1 | LUMP SUM | \$ | \$ |
| 21 | 610A-015 | Loose Riprap, Class 2 (Remove & Relocate) | 20 | SQUARE YARD | \$ | \$ |
| 22 | 610C-001 | Loose Riprap, Class 2 | 30 | TON | \$ | \$ |
| 23 | 610D-003 | Filter Blanket, Geotextile | 60 | SQUARE YARD | \$ | \$ |
| 24 | 614A-000 | Slope Paving | 15 | CUBIC YARD | \$ | \$ |
| 25 | 618A-000 | Concrete Sidewalk, 4" Thick | 2,366 | SQUARE YARD | \$ | \$ |
| 26 | 618A-001 | Concrete Sidewalk, 6" Thick | 119 | SQUARE YARD | \$ | \$ |

CONTRACT SCHEDULE

WITH SPECIAL REGARD TO SPECIFICATION SECTION 102.06, "PREPARATION OF PROPOSAL", **AS REVISED BY THE SPECIAL PROVISIONS**, THE FOLLOWING REPRESENTS THE BIDDER'S SCHEDULE OF CONTRACT UNIT PRICES FOR THIS PROPOSAL (bidder to complete below):

| LINE NO. | ITEM NO. | DESCRIPTION | QUANTITY & UNIT | | UNIT PRICE | AMOUNT BID |
|----------|----------|--|-----------------|-------------|------------|------------|
| 27 | 618B-003 | Concrete Driveway, 6" Thick (Includes Wire Mesh) | 429 | SQUARE YARD | \$ | \$ |
| 28 | 618C-001 | Detectable Warning Surface | 160 | SQUARE FOOT | \$ | \$ |
| 29 | 618D-000 | Curb Ramp | 102 | SQUARE YARD | \$ | \$ |
| 30 | 619A-002 | 18" Roadway Pipe End Treatment, Class 1 | 1 | EACH | \$ | \$ |
| 31 | 619A-004 | 30" Roadway Pipe End Treatment, Class 1 | 1 | EACH | \$ | \$ |
| 32 | 619A-100 | 15" Side Drain Pipe End Treatment, Class 1 | 1 | EACH | \$ | \$ |
| 33 | 620A-000 | Minor Structure Concrete | 5 | CUBIC YARD | \$ | \$ |
| 34 | 621A-011 | Junction Box, Type 1 or 1P | 1 | EACH | \$ | \$ |
| 35 | 621B-011 | Junction Box Units, Type 1 or 1P | 2 | EACH | \$ | \$ |
| 36 | 621C-036 | Inlets, Type S1 or S3 (1 Wing) (Modified) | 1 | EACH | \$ | \$ |
| 37 | 621D-015 | Inlet Units, Type S1 or S3 | 1 | EACH | \$ | \$ |
| 38 | 623B-121 | Concrete Curb, Type A (Modified) | 332 | LINEAR FOOT | \$ | \$ |
| 39 | 623C-004 | Combination Curb & Gutter, Type C (Modified) | 20 | LINEAR FOOT | \$ | \$ |
| 40 | 623C-015 | Combination Curb & Gutter, Type M-4 | 190 | LINEAR FOOT | \$ | \$ |
| 41 | 641R-510 | 3/4 Inch Water Meter and Box Reset | 1 | EACH | \$ | \$ |
| 42 | 641S-500 | Valve Box Reset | 2 | EACH | \$ | \$ |
| 43 | 645K-500 | Manhole Frame and Cover Reset | 3 | EACH | \$ | \$ |
| 44 | 650A-000 | Topsoil | 330 | CUBIC YARD | \$ | \$ |
| 45 | 652A-100 | Seeding | 1 | ACRE | \$ | \$ |
| 46 | 654A-000 | Solid Sodding | 2,960 | SQUARE YARD | \$ | \$ |
| 47 | 656A-010 | Mulching | 1 | ACRE | \$ | \$ |
| 48 | 659C-002 | Erosion Control Product, Type S2 | 100 | SQUARE YARD | \$ | \$ |
| 49 | 665J-002 | Silt Fence | 3,680 | LINEAR FOOT | \$ | \$ |
| 50 | 665O-001 | Silt Fence Removal | 3,680 | LINEAR FOOT | \$ | \$ |
| 51 | 665P-005 | Inlet Protection, Stage 3 or 4 | 1 | EACH | \$ | \$ |
| 52 | 665Q-002 | Wattle | 150 | LINEAR FOOT | \$ | \$ |

CONTRACT SCHEDULE

WITH SPECIAL REGARD TO SPECIFICATION SECTION 102.06, "PREPARATION OF PROPOSAL", **AS REVISED BY THE SPECIAL PROVISIONS**, THE FOLLOWING REPRESENTS THE BIDDER'S SCHEDULE OF CONTRACT UNIT PRICES FOR THIS PROPOSAL (bidder to complete below):

| LINE NO. | ITEM NO. | DESCRIPTION | QUANTITY & UNIT | | UNIT PRICE | AMOUNT BID |
|-------------------------|----------|---|-----------------|-------------|------------|------------|
| 53 | 680A-001 | Geometric Controls | 1 | LUMP SUM | \$ | \$ |
| 54 | 703A-002 | Traffic Control Markings, Class 2, Type A | 845 | SQUARE FOOT | \$ | \$ |
| 55 | 701H-001 | Solid Traffic Stripe Removed (Plastic) | 60 | LINEAR FOOT | \$ | \$ |
| 56 | 710A-163 | Class 10 Aluminum Flat Sign Panels (Type XI Background) | 40 | SQUARE FOOT | \$ | \$ |
| 57 | 710B-021 | Roadway Sign Post (#3 U Channel, Galvanized Steel or 2", 14 Ga Square Tubular Steel | 60 | LINEAR FOOT | \$ | \$ |
| 58 | 711A-000 | Roadway Sign Relocation | 1 | LUMP SUM | \$ | \$ |
| 59 | 740B-000 | Construction Signs | 168 | SQUARE FOOT | \$ | \$ |
| 60 | 740D-000 | Channelizing Drums | 100 | EACH | \$ | \$ |
| 61 | 740E-000 | Cones (36 Inches High) | 150 | EACH | \$ | \$ |
| TOTAL BID AMOUNT | | | | | | \$ |