

ARTICLE 5 – BASIS OF BID

5.01 Bidder will complete the Work in accordance with the Contract Documents for the following price(s):

NOTE: BIDS SHALL EXCLUDE SALES TAX AND ALL OTHER APPLICABLE TAXES AND FEES.

Item No.	Quantity & Units		Description	Unit Price		Total Price	
1.	1	L.S.	Mobilization, Including Bonds, Insurance, Etc.	\$	LUMP SUM	\$	
2.	1	L.S.	Traffic Control Plan And Implementation, Complete In Place For	\$	LUMP SUM	\$	
3.	45,000	S.Y.	135 Lb. Per S.Y. Plant Mix Wearing Surface (424-A), Including Tack, Complete In Place For	\$		\$	
4.	15,400	S.Y.	150 Lb. Per S.Y. Plant Mix Wearing Surface (424-A), Including Tack, Complete In Place For	\$		\$	
5.	22,500	S.Y.	Planing Full Width, 1"-2" Depth, Complete In Place For	\$		\$	
6.	6,230	S.Y.	Planing Full Width, 2"-3" Depth, Complete In Place For	\$			
7.	220	TON	Asphalt Leveling, Complete In Place For	\$		\$	
8.	15,730	S.Y.	Bituminous Surface Treatment, ALDOT Type "E", Complete In Place For	\$		\$	
9.	1,080	S.Y.	Wedge Milling Existing Pavement (0"-2"), Complete In Place For	\$		\$	
10.	170	L.F.	Remove And Replace Standard Curb, Complete In Place For	\$		\$	
11.	70	L.F.	Remove And Replace Curb & Gutter, Complete In Place For	\$		\$	
12.	30	S.Y.	Remove and Replace Concrete Sidewalk (4" Thick), Complete In Place For	\$		\$	
13.	90	S.Y.	Remove Asphalt Paving Due to Root Intrusion To Include Base Replacement Complete In Place For	\$		\$	
14.	30	S.Y.	Remove and Replace Concrete Driveway (6" Thick with Fiber Mesh), Complete In Place For	\$		\$	
15.	15	C.Y.	Crushed Aggregate Base, 6" Thick, Type B, Complete In Place For	\$		\$	
16.	780	L.F.	Machine Grading Shoulder, Complete In Place For	\$		\$	
17.	65	C.Y.	Borrow Material (Topsoil), Complete In Place For	\$		\$	
18.	50	S.Y.	Solid Sodding, Fertilizer, Water, Etc., Complete In Place For	\$		\$	

Item No.	Quantity & Units		Description	Unit Price		Total Price	
19.	65	EA.	Sewer And Water Manholes Adjusted To Grade, Complete In Place For	\$		\$	
20.	70	EA.	Water And Gas Valve Boxes Adjusted To Grade, Complete In Place For	\$		\$	
21.	110	L.F.	Cleaning and Sealing Concrete Pavement, Type 1, (Joints), Complete In Place For	\$		\$	
22.	4,520	L.F.	Solid Yellow, Class 2, Type A Traffic Stripe (5" Wide), Complete In Place For	\$		\$	
23.	310	L.F.	Solid White, Class 2, Type A Traffic Stripe (5" Wide), Complete In Place For				
24.	2,510	S.F.	Traffic Control Markings, Class 2, Type A, Complete In Place For	\$		\$	
25.	210	S.F.	Traffic Control Legends, Class 2, Type A, Complete In Place For	\$		\$	
26.	4,080	L.F.	Temporary Solid Stripe, Complete In Place For	\$		\$	
27.	370	S.F.	Temporary Traffic Control Markings, Complete In Place For	\$		\$	
28.	1,300	L.F.	Removal of Existing Solid/Broken Traffic Stripe (All Types), Complete In Place For	\$		\$	
29.	210	S.F.	Removal of Existing Traffic Control Markings/Legends (All Types), Complete In Place For	\$		\$	
30.	1	L.S.	General Contingency Allowance	\$	LUMP SUM	\$	200,000.00
TOTAL BID						\$	

Bidder acknowledges that (1) each Bid Unit Price includes an amount considered by Bidder to be adequate to cover Contractor's overhead and profit for each separately identified item, and (2) estimated quantities are not guaranteed, and are solely for the purpose of comparison of Bids, and final payment for all unit price Bid items will be based on actual quantities, determined as provided in the Contract Documents.

Bonds required under Paragraph 6.01 of the General Conditions will be based on the Contract Price.

ARTICLE 6 – TIME OF COMPLETION

6.01 Bidder agrees that the Work will be substantially complete and will be completed and ready for final payment in accordance with Paragraph 15.06 of the General Conditions on or before the dates or within the number of calendar days indicated in the Agreement.

6.02 Bidder accepts the provisions of the Agreement as to liquidated damages.